

Fruitville Road Widening from Debrecen Road to Lorraine Road

CIP # 95853

Last updated: October 2020

PROJECT SCHEDULE

Design Start

September 2020

Design Finish

September 2021

Construction Start

TBD

Construction Completion

TBD

Project Description

This project will include a preliminary engineering design report, roadway design plans, permitting and right-of-way analysis for a complete 4-lane divided urban arterial roadway extension from Debrecen Road to Lorraine Road, approximately 1.5 miles in length. The project includes adding two (2) through travel lanes, 5' sidewalks on both sides, 7' buffered bicycle lanes on both sides, roadway lighting, median, and landscaping with a closed drainage system. It also includes stormwater facilities and drainage ponds to accommodate the roadway improvements. An intersection control plan will be evaluated to determine the type of traffic signalization or possible roundabout configuration at the future extension of Lorraine Road. Also planned are utility infrastructure extensions for potable water and reclaimed water services.

This Capital Improvement Project (CIP) is planned for design only. Construction is currently not funded in the 5-year CIP.

PROJECT DETAILS

Design Consultant

Stantec Inc.

Design Contract Cost

\$1,380,000.00

Contractor

TBD

Construction Contract Cost

TBD

COUNTY PROJECT MANAGER(S)

Design

Peter Peduzzi
ppeduzzi@scgov.net

Construction

TBD

Project Progress/ Status

The project design and permitting were awarded by the Sarasota County Commission as an Interlocal Agreement with Windward at Lakewood Ranch Community Development District on August 26, 2020. Design progress is underway with a virtual Public Meeting planned for October 2020.

